

QUESTIONS FROM BIDDERS
WATER TREATMENT PLANT FILTERS REHABILITATION (FILTERS 1, 2, 3, & 7)
FOR
CITY OF CARTERSVILLE, GEORGIA

W&S Project No. 027-16-120

Bid Date: WEDNESDAY NOVEMBER 14, 2018 @ 2:00 PM

Updated:

10/16/2018

<i>Question #</i>	<i>Question</i>	<i>Answer</i>
1	What is the Engineer's cost estimate for the project	\$ 850,000.00 Dollars
2	Will there be a pre-bid conference?	No, there will not be a pre-bid conference.
3	If not who do I contact to schedule a site visit?	Daniel Duke (404-821-6637)
4	Section 01 10 00 Summary 1.3, D, 2, During summer months (May 1st to September 30th) no filters may be out of service, does the 365 day contract time include these 5 months we cannot work?	This is not correct and will be clarified by addenda. There are no time limits on when filters can be out of service, but there is a limit of the number of filters that can be out of service. Only one (1) filter can be taken out of service at any time. There are no restrictions on when the Contractor can work during 365 day contract time.
5	Invitation for Bids list liquidated damages at \$500 per day but the contract form has it at \$1,000 per day, which is correct?	The liquidated damages are \$500 per day. This will be clarified by addenda.
6	Section 01 10 00 1.8, C, states the warranty period shall begin when all work is complete. Because no work can be performed during the summer months it is possible filter 1 could be complete and in operation for almost a year before all work is complete. Should this cause a long lead time between filters placed into service would you consider separate warranty periods?	No, there will only be one (1) warranty period.
7	Are any modifications to the controls required?	No, there will not be any modifications to filter controls in this contract.
8	Please provide a copy of the Pre-Negotiated scope on the filter rehabilitation from Leopold.	The Filters and Media RFP and Leopold proposal, including scope, are included in the bid set of specifications under Appendix A.
9	Please confirm that the contractor is to saw cut and remove a section of the original structural filter slab in filter #7 for the installation of the new 6" Air line as shown on sheet M-02, M-03 Section "C". Also, please provide the as-builts to confirm the depth of this filter slab?	That is correct, the existing slab in Filter #7 is to be saw cut to allow for installation of 6" air pipe. See details and notes on Drawings M-01, M-02, M-03, S-01, and S-02. Per the Filter #7 record drawings the existing slab is supposed to be 12" thick. This same method was used for installation of air pipes in Filters 4, 5, and 6. Record drawings for all Filters will be provided to the successful low bidder.
10	Please confirm that the Detail shown above the Notes Section in the lower right-hand corner of S-02 is the detail for the Pipe Penetration repairs required on the unit price bid item.	Yes, the detail and notes together form Detail No.6 on Drawing S-02, and this is the detail for unit price bid item (Item No. III-5 on the Bid Form)
11	Can you forward the Plant address and contact information for scheduling a site visit to the Cartersville WTP?	Contact Daniel Duke (Plant Manager) at 404-821-6637 to schedule site visits. The plant address is: 237 Allatoona Dam Road Cartersville, GA 30120
NOTES:	1. Company Names and Trade Names have been removed from the questions. The answers contain trade names only to refer to existing installations. These inclusions do not represent an endorsement of the product or the company. 2. Questions from sales representatives have been edited where appropriate for brevity. 3. Questions from General Contractors have been left untouched. 4. Significant Changes in answers previously posted are marked in red.	